

**"This is only the scope of work for the project. For more information, interested parties should contact Procurement at [purchasing@stpgov.org](mailto:purchasing@stpgov.org) to ensure receipt of a full bid package, to be listed as a plan holder and to ensure any addenda to the bid package are received."**

This is a Capital Improvement Project. The work specified in this project will require the contractor to remove existing 160' of 30" CMP and replace it with 160' of 30" Polymer Coated Corrugated Metal Pipe (PCCMP). Work shall also include removal and replacement of existing wood fence (6' x 100'), move an equipment shed out of construction area and the set back to its original location and install sod to all disturbed areas.

Specifications for work are as follows:

All pipe shall be 30" PCCMP and shall be installed per LA DOTD Standard Specifications for Roads and Bridges, Section 701. Work shall include all straps and bands required to join pipe and all joints are to be wrapped in geotextile fabric. Soil around pipe shall be compacted and graded to drain. All existing sewer tie-ins or yard drains shall be tied in at no direct pay. All debris is to be removed at no direct pay.

All labor and materials necessary to remove and re-install fence, in kind. Fence dimensions are 6' x 100'. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 705. All debris is to be removed at no direct pay.

Contractor is to verify all dimensions and lengths.

Work shall include all necessary signage, barricades and flagmen per LA DOTD Standard Specifications for Roads and Bridges, Section 713 and mobilization of equipment per Section 727.

The contractor will have 30 days to complete the project from the date stated in the Notice to Proceed issued by the Parish.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.