

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at purchasing@stpgov.org to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

The Parish requires a Contractor to remove all floating solids from the Castine Lift Station and dispose of them in accordance with all state and federal regulations. The lift station measures 16' x 16' and the floating solids are estimated to be 4' thick. The Contractor shall provide the Parish with a manifest for each load removed and disposed of and shall indicate the ultimate disposal location.

The time period for completion of the project is thirty (30) calendar days from Notice to Proceed issued by the Parish.

A Quote Guarantee **is** required for this project.