

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at purchasing@stpgov.org to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

Scope of Works:

The Contractor must provide all labor, equipment, tools and materials to perform the following work:

Remove existing portion of drive, curb and head wall that is broken and has moved.

Install concrete headwalls per the contract drawing. Head wall is to be 6" thick by 34" tall and 10'6" long and constructed of 3,000 psi concrete, class M per LA DOTD Standard Specifications Section 805, 2016 edition.

Work shall include #5 rebar set on a 6" x 6" grid both ways.

Provide granular fill behind head wall to fill in area that has washed out.

Install 6" concrete drive per the contract drawings. Drive shall include wood expansion material, 4' x 3"x 3" curb and be constructed of 3,000 psi concrete, class M per the LA DOTD Standards for Roads and Bridges, Section 706, 2016 Edition.

The Contractor shall provide all signage and barricades. The Contractor shall remove all debris at no direct pay.

The Contractor shall have thirty (30) days to complete project upon issuance of the Notice to Proceed by the Parish.

All supervision, labor, materials, supplies, equipment, and permits required to complete the work shall be included in the lump sum quote.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.