

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at purchasing@stpgov.org to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

Scope of work/Services

Contractor shall supply all labor and materials necessary to remove and replace two (2) concrete road panels. Road panels shall be 8" thick and be constructed with 4000 psi, Class B concrete with fiber mesh. Work shall include all necessary saw cuts to remove the existing panels without damaging the adjacent panels. All work shall be done in accordance with LA DOTD Standard Specifications for Roads and Bridges, Section 602, 2016 Edition. The panel dimensions are 12' x 16' and 18' x 21'. Both panels have been marked by the Parish Inspector with white paint. All debris shall be removed from the project at no direct pay.

The Contractor shall provide all necessary construction signs, barricades and flagmen per the LA DOTD Standard Specifications for Roads and Bridges, Section 713, 2016 Edition.

The Contractor shall verify all dimensions prior to bidding on the project.

The Contractor shall have 30 days to complete the project upon issuance of the Notice to Proceed by the Department of Public Works.

A Quote Guarantee **is not** required for this project.

All supervision, labor, materials, supplies, equipment, and permits required to complete the work shall be included in the lump sum quote.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.