

"This is only the scope of work for the project. For more information, interested parties should contact Procurement at [purchasing@stp.gov.org](mailto:purchasing@stp.gov) to ensure receipt of a full project package, to be listed as a plan holder and to ensure any addenda to the project package are received."

2.1 Scope of work/Services

The Parish requires a Contractor to supply and install 40 LF of HDPE drainage pipe, A/H 54" (1350 mm) AASHTO M-294 2306 PE. Work shall include all necessary saw cuts to install the pipe forming two spliced butt joints. Contractor shall bed the pipe in 6" of granular fill and install granular fill in 12" lifts up to the top of the pipe. Each lift must be compacted with a vibratory compactor before the next lift is installed. Spoils will be used to fill from top of pipe to top of existing grade. Install two Mar Mac couplers provided by the Parish. Install sod to all disturbed areas. Removal of all debris is to be done at no direct pay. Contractor is responsible to verify all quantities. Work location is Country Club Drive (D04AW03011) in Covington, Louisiana (S37-T7S-R11E).

The time period for completion of the project is thirty (30) calendar days from Notice to Proceed issued by the Parish.

All supervision, labor, materials, supplies, equipment, and permits required to complete the work shall be included in the lump sum quote.

A Quote Guarantee **is not** required for this project.

Any work that may be reasonably inferred from the specifications or drawings as being required to produce the intended result shall be supplied whether or not it is specifically called for. Work, materials or equipment described herein which so applied to this project are covered by a well-known technical meaning or specification shall be deemed to be governed by such recognized standards unless specifically excluded.